

Metropolitan Edison Company Post Office Box 480 Middletown, Pennsylvania 17057

Writer's Direct Dial Number

June 17, 1981 LL2-81-0158

JUL IPIC -----8 Pil w N -11

TMI Program Office Attn: Mr. L. H. Barrett, Deputy Director U. S. Nuclear Regulatory Commission c/o Three Mile Island Nuclear Station Middletown, Pennsylvania 17057

Dear Sir:

Three Mile Island Nuclear Station, Unit 2 (TMI-2) Operating License No. DPR-73 Docket No. 50-320 Interim Solid Waste Staging Facility (ISWSF) TER

Enclosed herein for your review and approval is the Technical Evaluation Report and the Design Criteria for the Interim Solid Waste Staging Facility (ISWSF). These documents include resolutions to your comments on the Design Criteria, previously submitted for your review. Completion of the ISWSF is scheduled for October, 1981. Your timely consideration of this matter would be greatly appreciated since this facility is currently under construction.

Sincerely,

G. K. Hovey Vice-President and Director, TMI-2

GKH:RBS:vif

Attachments

cc: Dr. B. J. Snyder, Program Director, TMI Program Office



8106230360

L'etropolitan Edison Company is a Member of the General Public Utilities System.

13587-2-G01-105

*

....

DESIGN CRITERIA DOCUMENTS

COVER SHEET

INTERIM SOLID WASTE STAGING FACILITY FOR GPU SERVICE CORPORATION THREE MILE ISLAND-UNIT 2

JOB NO: _____13587

...

DISCIPLINE:

GENERAL

Corrent Correction of the						
		•				
3	5/4/20	Revised as Noted and Issued for Use Upon GPUSC Approval	Ers	HALA	fuil	
2	12/3/80	Revised as Noted and Issued for Use Upon GPUSC Approval	201	WHH	ful	(t)
1	7/2/20	Reissued for Use Upon GPUSC Approval	RPG	Ers	Ew	RED!
o	7/1/42	Issued for Use Upon GPUSC Approval	R.P.M	Ers	Dent	HOT IFPFELIE:
REV. NO.	DATE	REVISION DESCRIPTION	DRIGINATOR	SUPV	PROVAL	GPUSC
	all and the state	8100230304				de molueine artes a

SHEET	LATEST REV.	SHEET	LATEST REV.	SHEET	LATEST REV.	SHEET	LATEST REV.	SHEET	LATEST REV.	SHEET	LATEST REV.	SHEET	LATES REV.
				•				andra a star Si an an					
1	1										意思错		
1	٢					臺灣於南部							
2	3	•											
3	3							and and a second s			Allowed		
4	3		N.										and the
5	3						Alexandra (
6	3												1000
7	2												
der seine													
								and the second		distant ser			
					in Differences		04						1993
					An IEDA				The state of the				
	diarang banda												11-11-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-
				•			all and the						
							All the state				•		
		and the second sec		はたいに語									
「日本で													
•											新日前 南		
	•												N. Alara
									(arte and)	•			
	的现在分												
i anti	in the second					Electro							Sec. 1
						a the add				tin Station			1
		and the second second	Tation of						de anti-				and and a feature
				and the second									
						Line di					1.2.2.4.2.1		1.00
	1057												and the second
								riesk den e Ministeria		nde son den Geren met der			
				la de la sec Texterne de la									
								Careford - Se			10007		
F	Del		ESIGN	CRITER		UMENT	s			DISCIPL	13587		REV.
BEC	MIL		DEL	CION CT	ATUCC	UCET			1.00		GENERA		1 7

DESIGN CRITERIA

.

FOR

INTERIM SOLID WASTE

STAGING FACILITY

FOR

GPU SERVICE CORPORATION

THREE MILE ISLAND - UNIT 2

CONTENTS

		Pao	e
1.0	FUNCTION		
2.0	SCOPE	· · · · · · · · · · · · · · · · · · ·	
3.0	FACILITY DEFINITION	i	
4.0	FUNCTIONAL REQUIREMENTS	2	
5.0	FACILITY DESIGN REQUIREMENTS	3	
-			
TABL			

i

5-1 DESIGN STORAGE REQUIREMENTS

-

7 | 1

.

3

3

DESIGN CRITERIA

.

FOR

INTERIM SOLID WASTE STAGING FACILITY

1.0 FUNCTION

The Interim Solid Waste Staging Facility (ISWSF) is to be used for the collection and temporary storage of low level solid or solidified waste packages. All waste packages in the ISWSF are assumed to be completely prepared for shipment. Provisions for radiation surveys of waste packages and the taking and analyzing of swipes from the waste packages are provided. The Interim Solid Waste Staging Facility will be sized to accommodate 6 months of waste generation from both Units 1 and 2 in the quantities as shown in Table 5-1 without shipment for offsite disposal.

2.0 SCOPE

The Interim Solid Waste Staging Facility will be a simple facility consistent with its passive function. There will be a slab with curbs and sumps to contain any liquids collected within the facility. A noncombustible roof will be supported on columns. Electric power will be supplied to the facility for sump heaters, lights, and utility outlets. The facility will have one truck bay to facilitate loading waste packages onto trucks for shipment. There will be a fence completely surrounding the facility.

3.0 FACILITY DEFINITION

3.1 FUNCTION

The Interim Solid Waste Staging Facility provides a location for the collection of waste packages. It performs the passive functions of protecting waste packages from precipitation and providing a facility which eases loading of waste packages on trucks. The Interim Solid Waste Staging Facility performs no active functions.

3.2 MAJOR COMPONENTS LIST - SEE SECTION 2.0, SCOPE

3.3 INTERFACES

There are six interfaces associated with this facility.

(1) The facility must interface with the onsite material handling equipment which will be used to bring waste packages into the facility. Material handling into and within the ISWSF will be done with forklifts. There will be at least one ramp into the facility.

> Page 1 Rev. 3

-

3

3

- (2) The ISWSF must interface with trucks and shipping casks used to transport waste packages offsite. There will be one truck bay adjacent to the ISWSF, which will allow loading of a standard flatbed trailer or enclosed van by a forklift. Ramps will exist over the curbs.
- (3) The ISWSF will be completely surrounded by an isolation fence. On the east side, the isolation fence is also the station fence.
- (4) An interface with an existing electrical system will be required to provide power for lights and utility outlets.
- (5) An interface will exist between the ISWSF and the existing plant to assure that fire protection and detection are adequate.
- (6) An interface with the existing in-plant paging system will be provided.

4.0 FUNCTIONAL REQUIREMENTS

4.1 ACCESSIBILITY

In addition to the access requirements identified in Section 3.3, Interfaces, there is a need for ready access within the Interim Solid Waste Staging Facility. Access within the facility is required to assure that material handling operations proceed quickly to assure operator exposures are ALARA. There may also be a need for temporary shield walls within the facility to achieve ALARA operator exposures.

4.2 MAINTAINABILITY

This facility shall require no preventive maintenance for at least five years. The slab and columns shall be epoxy coated to a height consistent with the maximum depth for water accumulation.

4.3 PERSONNEL

Personnel will be needed in the Interim Solid Waste Staging Facility to do material handling. The minimum number of operators needed to perform the activities will be assigned to assure that total exposure is ALARA. Only those personnel actively involved in the material handling activities should be inside the fence enclosing the ISWSF.

4.4 SAFETY

Waste stored in the Interim Solid Waste Staging Facility will be in a nondispersible form, since it will be a solid and contained within a sealed container or fixed in place such that radionuclides cannot become airborne. Regulation 10 CFR 20.105 limits the radiation levels in unrestricted areas. Regulation 40 CFR 190 further limits the yearly radiation dose to any member of the public due to all fuel cycle activities, including direct radiation. Compliance with these regulations will assure that the facility will not have an unacceptable impact on public health and safety.

The site's Radiation Protection Plan, which implements the requirements of 10 CFR 20.1(c), will assure that operator exposures associated with the Interim Solid Waste Staging Facility are ALARA.

Compliance with 40 CFR 190 is ensured by meeting a maximum dose rate of 20 mr/year at (1) the site boundary (river shoreline) assuming an occupancy factor of no more than 67 hours per year (see Regulatory Guide 1.109), or (2) the nearest residence. A dose rate of 0.6 mr/hr is used at the fence separating the ISWSF from areas surrounding it.

5.0 FACILITY DESIGN REQUIREMENTS

5.1 GENERAL REQUIREMENTS

The input to the Interim Solid Waste Staging Facility will be packages of solid or solidified wastes ready for shipment. The quantity and radiation levels of the wastes from both Units 1 and 2 used for facility design are presented in Table 5-1. The values specified in Table 5-1 are to be used for design purposes. Waste packages of similar materials but of different quantities and radiation levels may be stored in the facility provided all the requirements specified in this design criteria are met. Activities occurring in the facility include the handling of waste packages, performance of radiation surveys of the waste packages, and the taking and counting of swipes of the waste packages.

The Interim Solid Waste Staging Facility will allow separation of Unit 1 wastes from Unit 2 wastes.

5.2 CODES, STANDARDS, AND REGULATIONS

5.2.1 Federal

5.2.1.1 10 CFR Part 20, "Standards for Protection Against Radiation"

5.2.1.2 40 CFR Part 190, "Uranium Fuel Cycle Standard"

5.2.1.3 United States Nuclear Regulatory Commission Regulatory Guide 1.109 - Calculation of Annual Doses to Man from Routine Releases of Reactor Effluents for the Purpose of Evaluating Compliance with 10 CFR Part 50, Appendix I (Rev. 1, October 1977)

5.2.2 Industry

The facility will be designed in accordance with the applicable portions of the following industry and state codes:

5.2.2.1 American Institute of Steel Construction (AISC), "Specification for the Design, Fabrication and Erection of Structural Steel for Buildings," November 1, 1978

Page 3 Rev. 3

5.2.2.2 American Iron and Steel Institute (AISI), "Specification for the Design of Cold-Formed Steel Structural Members," 1968 Edition, with commentary dated 1970 and supplement dated 1971

5.2.2.3 American Concrete Institute (ACI), "Building Code Requirements for Reinforced Concrete, (ACI 318-77)

5.2.2.4 Building Officials and Code Administrators International, "The BOCA Basic Building Code," 1978

5.2.2.5 Metal Building Manufacturers Association, "Recommended Design Practices Manual," 1974

5.2.2.6 National Electric Code (NEC)

5.2.2.7 Pennsylvania Code for Fire and Panic.

5.3 INTERLOCKS AND ADMINISTRATIVE CONTROLS

Administrative controls are required to ensure that material stored in the ISWSF meets all the requirements specified in this design criteria. These controls should also assure that the smearable contamination on each package's outer surface is below the regulatory limit for shipping. There will be no interlocks in this facility.

5.4 MATERIALS

The slab and curb of the ISWSF will be concrete finished with epoxy. The roof will be metal standing seam with factory-applied protective coating. Shield walls will be either poured concrete or grout-filled concrete masonry units. All wall surfaces facing storage areas shall be finished with epoxy to a height of 8 inches. Above 8 inches the outside of the walls shall be painted with a sealer. Structural steel columns, where exposed to storage areas, shall be finished with epoxy to a height of 8 inches. Above 8 inches and all other steel columns and roof framing shall receive standard shop-applied primer and field-applied protective finish. All fencing materials shall be galvanized.

5.5 LAYOUT REQUIREMENTS

5.5.1 Location

The location and size of the ISWSF is determined by

- number of containers based upon 6 months storage (Table 5-1)
- space available
- configuration required for separation of Unit 1 and Unit 2 waste
- storage area requirements based upon pyramidal vertical stacking
- minimum clearance requirements to overhead power lines
- sufficient space for forklift operation

Page 4 Rev. 3 3

3

3

- required topography to facilitate incorporation of the truck bays
- shielding requirements to meet ALARA and boundary dose considerations.

The location of the ISWSF also governs the radiation level of packages which may be stored there without shielding. This is so since its location will establish the distance to the fence which must surround the facility.

5.5.2 Shielding

Partitions of either poured concrete or grout filled concrete masonry units will be used to reduce the exposure to the personnel in the unshielded areas and meet the site boundary and unrestricted boundary levels.

5.6 STRUCTURAL REQUIREMENTS

5.6.1 The facility shall consist of an open-sided metal building designed to satisfy the following requirements:

- a. The roof live load (snow load) shall be 30 psf applied to the horizontal projection of the roof area.
- b. The wind load shall be applied and proportioned as horizontal and uplift forces in accordance with Section 4 of Metal Building Manufacturers Association (MBMA), "Recommended Design Practices Manual" and shall be 20 psf.
- c. Seismic loads shall be determined in accordance with the BOCA Basic Building Code for Seismic Zone 1.
- d. The combinations of loads and allowable stresses to be considered in the design of all members of the structure shall be in accordance with Section 7 of the MBMA, "Recommended Design Practices Manual."

5.6.2 The floor slab shall be designed for a live load of 1000 psf. The wheel loads for the fork lift will also be considered in the slab design.

5.7 ELECTRICAL REQUIREMENTS

Electrical power will be provided to supply sump heaters, lighting, and receptacle loads. The power will be derived from the 13.2 kV overhead lines on the east side of the site. A 120/208 volt service will be provided from a panelboard within the facility. Outlets will be provided for portable sump pumps. A lighting level of 10 FC will be provided. All electrical systems and metal structures will be grounded. The in-plant paging system will be extended to serve the facility. In the event that fire detection is included in the facility, an alarm circuit will be routed up to the fire protection console in the main control room.

5.8 FIRE PROTECTION REQUIREMENTS

A fire hazards analysis will be performed. If required, fire detection will be by a combination of thermal and smoke (obscuration type) detectors. If provided, the alarms will tie into the control room and will be monitored at all times. Fire extinguishing will be by a firehose from fire hydrant house FS-U-19, located approximately 250 feet from the facility.

Table 5-1

.

* DESIGN STORAGE REQUIREMENTS

Unit ⁻	Quantity (per month)	Container/ Trash Type	Radiation Level
1	37	55 gal drum/compacted trash	up to 50 mr/hr
1	19	55 gal drum/compacted trash	50 to 100 mr/hr
1	15	55 gal drum/compacted trash	100 to 200 mr/hr
1	4	55 gal drum/compacted trash	200 - 400 mr/hr
1	1	4'x4'x7' box/compacted trash	up to 200 mr/hr
1	10	50 ft ³ liners/solidified evaporator bottoms	200 - 500 mr/hr
2	9	55 gal drum/solidified radiac waste	up to 100 mr/hr
2	16	55 gal drum/compacted trash	0 to 1 mr/hr
2	6	55 gal drum/compacted trash	1 to 2 mr/hr
2	11	55 gal drum/compacted trash	2 to 5 mr/hr
2	9	55 gal drum/compacted trash	5 - 20 mr/hr
. 2	5	55 gal drum/compacted trash	20 - 100 mr/hr
2	2	55 gal drum/compacted trash	100 - 500 mr/hr
2	1	55 gal drum/compacted trash	500 - 1000 mr/hr
2	1	55 gal drum/compacted trash	1000 - 2000 mr/hr
2	2	4'x4'x7' LSA boxes	0 - 1 mr/hr
2	• 2	4'x4'x7' LSA boxes	1 - 2 mr/hr
2	3	4'x4'x7' LSA boxes	2 - 10 mr/hr
2	3	4'x4'x7' LSA boxes	10 - 20 mr/hr
2	3	4'x4'x7' LSA boxes	20 - 100 mr/hr
2	· 1	4'x4'x7' LSA boxes	100 - 200 mr/hr

Page 7 Rev. 2 E State

2

.

2

DISTRIBUTION LIST FOR

THI-2 PROJECT DESIGN CRITERIA

COPY NO.	PERSON	TINE .	COPT NO.	PERSON	IITE
۱	J. W. Thissing	Project Manager	25	E. D. Fuller	THI-2 Licensing, CPU
2	R. L. Rider	Project Engineer	26	W. E. Riethle, III	THI-2 Env. Import Assessment, GPU
<u>، </u>	R. W. Jackson	Assistant Project Engineer	27	B. Elem	Managar, Plant Eng., GPU
•	W. H. Nouse, II	· G. S Muclear/Licensing	28	H. K. Pastor	Ngr., Recovery Programe, GPU
s	T. H. Patterson	G. S 70/Mach.	29		THI-2 Master Plant File, GPU
·	J. S. Whitereft	G. S Civil/Arch.	30	L. Smith	Paraippany DDCC Supv., GPU
1	D. W. Douds	0. S CS/Electrical	31	J. R. Thorps	Director Env. Mealth & Safety, GTU
•	C. J. Penfield	Electrical Group Leader	32		
9	C. H. Les	Arch. Group Laader	33		
10	E. T. Smith	Lic. Group Lasder	34		•
n	R. E. Herriman	Proj. Quality Engineer	36	\sim	
12	P. Perez	Chief - Arch.	37		
13	J. C. Judd	Chief - Nuclear	38	/	
14	B. L. Welton	Project Administrator	39	N	
15	R. G. Lewrence	Planning and Control	40		
16	R. E. Welker	Lead Site Lisison Engineer	41		
17		Project Library	42		
18	P. R. Clark	Exec. Vice President, GPU	43		
19	N. C. Kezanse	QA Manager, GPU	44		
20	J. C. DeVine, Jr.	Hgr., Bacovery Eng. THI-2, GPU	45	•	
21	J. J. Barton	Director, Site Operations, GPU	46		
22	R. F. Wilson	Director, Technical Functions, GPU	47		••
23	R. W. Heward, Jr.	Hgr., Radiological Controls, CPU	40		
24	G. K. Hovey	Director, TMI-2, GPU	49		

UPON RECEIVING AND INCORPORATING THESE CHANCES TO THE THI-2 PROJECT DESIGN CRITERIA MANUAL, PLEASE SICH AND RETURN THE ENTIRE SHEET TO THI-2 PROJECT ADMINISTRATOR, BECHTEL NORTHERN, GAITHERSBURG, LOCATION 2D-1

-

.....

....

Please check contents of your sseigned Menual against the enclosed page revision status sheets for each Criteris. Request any needed material from the THI-2 Project Administrator. Your Signature on this receipt attests to the currency and completeness of your menual. .

Date

Revision

TECHNICAL EVALUATION REPORT

FOR

INTERIM SOLID WASTE STAGING FACILITY

FOR

GPU SERVICE CORPORATION

THREE MILE ISLAND - UNIT 2

Bechtel Northern Corporation Bechtel Job 13587 Revision 3 May 1981

.



.

di

. ..

SHEET	LATEST REV.	SHEET	REV.	SHEET	REV.	SHEET	REV.	SHEET	LATEST REV.	SHEET	REV.	SHEET	REV
1	0											an saite	
11	0.												
1-1	0											and the	
1-2	0												
2-1	0										9-724		
2-2	3												
2-3	3												
2-4	0	N BARRA											
Teble 2-1	0	PEASE/											
F181	0												
F18.	0	10.23		and a state									
3-1	0												
3-2	0		建建筑建			and and a second se							
3-3	2												120-00 24-077
3-4	3												
3-5	2												
3-6	2	in and the						• 11:17					
3-7	2						ansay date						
3-8	2										Sec. 1		
Table 3-1	0								A State and				
4-1	0												
Table	0	de la come	$\frac{1}{ 0 } \frac{ 0 }{ 0 } \frac{ 0 }$						1000				
5-1	0											17 July 1	-
					land the								Sec.
							Sinchaferin					4月1日1日	
			Alexandra (and serve						and the		
													New York
	STERNE STERNE	an and a star				an analasian					and the second		1.101
								and the					a stanta
				Salara es			The second					aner terito	1. Spice
(in) day													
					ta da bar Televitari								
							San Angel						S. C. S.
							New York						
]		1775 M			96 <u>52</u> 43	CL THE S						
TEC	ATTEL		REV	Techni	ATUS SH	EET aluati	on Repo	rt for		JOB/GR	OUP 13: INE Nuclear	587	REN
~	ed De	CUMEN	T TITLE:	Incer	um soli	a wast	e Stagi	ng Faci	lity			1	3

TABLE OF CONTENTS

. .

				Page
1.0	INTRO	DUCT	ION	1-1
	1.1	Gene	ral .	1-1
	1.2	Organ	nization of Report	1-1
	1.3	Conc	lusion	i-i
2.0	FACIL	ITY I	DESCRIPTION	2-1
	2.1	Purpo	ose of the Facility	2-1
	2.2	Summa	ry Description	2-1
		2.2.1	Location	2-1
		2.2.2	l Design Basis	2-1
		2.2.3	Building Description	2-1
		2.2.4	General Arrangement	2-2
	2.3 1	Major	Systems	2-3
	2.4	Mater	ial Handling Operations	2-3
		2.4.1	Description of Packages	2-3
		2.4.2	Unloading and Stacking of the Packages	2-4
		2.4.3	Removal of Packages	2-4
	Table	2-1	Design Storage Requirements	
	Figure	2-1	Recovery Facilities Plan	
	Figure	2-2	ISWSF General Arrangement	
3.0	TECHNI	CAL	EVALUATION	3-1
	3.1 L	icen	sing Issues	2_1
	3.2 D	lose	Assessment	3-1
	3	.2.1	Off Site	3-1
	3	.2.2	On Site	3-5
	3.3 0	ccupa	ational Exposures	3-5
	3	.3.1	Design Features	3-6
	3	.3.2	Man-Rem Estimate	3-6
	Table	3-1 	Area Radiation Levels with Six Months Design Basis Inventory	
4.0	COMPAR IMPACT	ISON STAT	WITH PROGRAMMATIC ENVIRONMENTAL TEMENT (PEIS)	4-1

i

Table 4-1 Contents of Staging Facility

EA	CAPPONT DIVATING AN			
3.0	SAFELY EVALUATION			6 9
Contraction and				2-1
	5 1 Packalant C. J.C.			
2 C 2 / 2 /	J.I ICCNDICAL SDECIFICATions			5-1
		a spin and the second of		3-1
1	5.2 Unreviewed Safety Questing			
	Sie Galerieu Salety Question			5-1
			and the second second second	

1

• *

.....

.

1.0 INTRODUCTION

1.1 General

The cleanup effort at Three Mile Island Unit 2 is expected to result in the generation of a significant quantity of low level (Note 1) solid or solidified radioactive waste. In addition, low level solid or solidified radioactive waste is also being generated in Unit 1. Due to limitations on low level radioactive waste disposal sites and limited onsite staging capacity, an additional facility for the collection and temporary staging of low level solid or solidified radioactive waste is needed.

The facility proposed to fulfill the need identified above is the Interim Solid Waste Staging Facility (ISWSF).

This Technical Evaluation Report (TER) demonstrates that the ISWSF has been designed and will be operated in such a manner as to provide assurance that:

- a. The health and safety of the public will be protected.
- Occupational exposures will be as low as reasonably achievable (ALARA).
- c. There will be no adverse impact on the environment.

1.2 Organization of Report

This report is organized in the format of a combined safety analysis and environmental report. Following this introduction, a description of the design and operational considerations is presented. This is followed by a discussion of the safety and environmental issues associated with the facility. A comparison of the ISWSF design with the Programmatic Environmental Impact Statement is presented next. The report concludes with the safety evaluation required by 10 CFR 50, paragraph 50.59, "Changes, Tests, and Experiments."

1.3 Conclusion

• *

The information provided in this report results in the following conclusions:

a. The ISWSF fulfills the need for a facility in which to temporarily stage low level solid or solidified radioactive waste.

Note 1. As used herein the term "low level" refers to the dose rate on contact with the waste packages as defined in Table 2-1. The term gives no indication as to the isotopic or elemental content of the package. b. The operation of the facility is not an unreviewed safety question as defined in 10 CFR Part 50, paragraph 50.59.

· · · ·

.

•••

.

2.0 FACILITY DESCRIPTION

2.1 Purpose of the Facility

The ISWSF is to be used for the staging of low level solid or solidified radioactive waste packages from both Units 1 and 2 prior to shipment offsite for disposal. The packages will be staged in the facility for up to 2 years.

- 2.2 Summary Description
- 2.2.1 Location

As shown on Figure 2-1, the ISWSF is located east of the Unit 2 turbine building and between the offsite transmission lines for Unit 2. It is surrounded by an outer fence which aids in restricting access to the area immediately surrounding the facility. Access to the area enclosed by the outer fence will be controlled by established plant procedures. The only activities occurring within this area will be those associated with the ISWSF.

2.2.2 Design Basis

The ISWSF has no safety design basis.

The facility is designed to provide a controlled but ready access for material handling operations to ensure that operator exposures are as low as is reasonably achievable (ALARA). The facility is sized to accommodate the wastes generated in 6 months from Units 1 and 2. The monthly waste generation rates used in the design are given in Table 2-1.

In addition, the ISWSF is designed to maintain the dose rate at the outer fence surrounding the facility at 0.6 mrem/hr, in accordance with 10 CFR Part 20, paragraphs 20.105(b)(2) and 20.202(a)(1). The facility is also designed to meet the requirements of 40 CFR Part 190 at the site boundary and beyond.

2.2.3 Building Description

The ISWSF, shown in Figure 2-2, is a non-seismic Category I, concrete floor slab, covered by a prefabricated metal roof. Shielding partitions of grout-filled concrete masonry units are used to satisfy the dose rate criteria specified in Section 2.2.2. A roof is provided to minimize the volume of rainwater entering the facility which could potentially become contaminated and thus require monitoring and processing. The roof also allows unloading and loading of trucks during adverse weather conditions.

An 8-inch-high curb is provided around the perimeter of the floor slab to contain any rainwater that may enter the building. Ramps are provided to allow passage of a forklift over the curb. The floor slab is sloped so that any water entering the facility will be directed toward one of the six sumps provided. With the use of portable pumps, water collected in these sumps will be disposed of in accordance

with established plant operation procedures. The sumps are provided with manually actuated heaters to facilitate disposal of collected water during the winter.

The floor slab, sumps, and curb are epoxy coated for ease of decontamination should the need arise. The exposed structural steel columns in the storage areas are also epoxy coated to a height of 8 inches for compatibility with the curb. The remaining portions of the steel columns and the roof framing have a protective finish. The shielding partition surfaces facing the storage areas are epoxy coated to a height of 8 inches and painted with a sealer above 8 inches. The outside surfaces of the partitions are painted with a sealer.

In addition to the outer fence surrounding the area around the ISWSF, there is an 8-foot-high inner fence provided around the unwalled sections of the facility (see Figure 2-2).

With the exception of small quantities of electrical cable associated with electrical power and the in-plant paging system, all materials used in the construction of the facility are noncombustible.

2.2.4 General Arrangement

The ISWSF consists of six basic areas: (1) loading/ unloading, (2) survey, (3) open staging, (4) Unit 1 shielded staging, (5) Unit 2 shielded staging, and (6) personnel monitoring/analysis. A discussion of these areas follows. The general arrangement of the facility is shown in Figure 2-2.

2.2.4.1 Loading/Unloading Area

The loading/unloading area consists of a truck bay, a ramp into the facility, and an area for the loading and unloading of a standard flatbed trailer or enclosed van by a standard forklift.

2.2.4.2 Survey Area

A survey area is provided to allow for radiation surveys of the waste packages prior to placing them on a truck for shipment off site. This area is separated from the truck bay and the open staging area by shield partitions.

2.2.4.3 Open Staging Area

The open staging area is separated from the survey area by a shield partition. For administrative purposes, it is divided into a section for Unit 1 wastes and a section for Unit 2 wastes. The Unit 1 and Unit 2 areas are flexible and shown in Figure 2-2 for illustration. These areas may vary throughout the life of the facility. These sections are separated by a portable barrier consisting of stanchions connected by a chain. Access routes, or aisles, with gates at the entrance, allow for the movement of the containers by a forklift to the appropriate area. It should be noted that the segregation of wastes by unit is not required by federal regulations. Rather, it is solely for utility administrative purposes.

2.2.4.4 Shielded Staging Areas

Shielded staging areas are provided in order to meet the dose rate limits specified in the design basis, Section 2.2.2. Separate shielded areas are provided in order to maintain separation between wastes from each unit. Access to these areas is by means of the aisles identified in Section 2.2.4.3. Access will be controlled by administrative procedures.

2.2.4.5 Personnel Monitoring/Analysis Area

The personnel monitoring/analysis area is a small cubicle at the end of the loading/unloading area. This area contains equipment for personnel monitoring and for the analysis of swipe samples of the waste packages.

2.3 Major Systems

The only systems provided for the operation of the ISWSF are electrical power for lighting, receptacles, sump heaters, and the in-plant paging system. None of these systems serve any safety-related function.

No radiation monitors are provided in the facility. This is because the facility is a radiological controlled area and access is controlled at the outer fence.

2.4 Material Handling Operations

2.4.1 Description of Packages

The packages to be staged in the ISWSF are of several types. These are described below.

Four 55-gallon drums of compacted trash and/or solidified radiac waste will be placed on 4-foot by 4-foot pallets. Depending on the weight of each drum, they may be banded together.

A single 50-cubic-foot liner of solidified evaporator bottoms will be placed on a 4-foot by 4-foot pallet. The dimensions of the liner are 4 feet in diameter and 4 feet high.

There will also be metal LSA boxes containing compacted trash satisfying the requirements of 10 CFR Part 71. The dimensions of the LSA boxes are 4 feet x 4 feet x 7 feet. These boxes will arrive at the facility with a spacer between each box to allow a forklift to readily lift the box.

13587-2-G03-105

All waste packages received in the ISWSF will be completely prepared for shipment. All counting, swiping, decontamination, and weighing will be done prior to the transfer of the packages to the ISWSF. Provisions have been included in the design of the ISWSF to allow additional counting and swiping in the ISWSF.

.... Unloading and Stacking of the Packages

The packages of waste will arrive at the ISWSF on either a standard flatbed trailer or in an enclosed van. Upon arriving at the facility, the vehicle containing the waste will be parked in the truck bay located in the loading/unloading area. At this point a 3,000-pound to 5,000-pound capacity forklift will unload the packages and transport them to the proper area of the facility.

Upon arriving at the proper location within the facility, the packages will be stacked. The pallets and boxes will be stacked no more than three high, which is consistent with current GPUSC practice. In general, the pallets will be stacked in a staggered manner. The LSA boxes will be stacked one on another with spacers.

The required lift height of approximately 10 feet is well within the 16-foot lifting height of the forklift. The capability of the pallets to carry the load has been checked for the design basis arrangement and has been found acceptable. The pallets are of four stringer design, with solid planking top and bottom.

2.4.3 Removal of Packages

2.4.2

When a package is removed for shipment, the reverse of the procedure described in the previous section will be followed.

TABLE 2-1

•

DESIGN STORAGE REQUIREMENTS

Unit	Quantity (per month)	Container/ Trash Type	Radiation Level
1	37	55 gal drum/compacted trash	up to 50 mrem/hr
1	19	55 gal drum/compacted trash	50 to 100 mrem/hr
1	15	55 gal drum/compacted trash	100 to 200 mrem/hr
1	4	55 gal drum/compacted trash	200 - 400 mrem/hr
1	1	4'x4'x7' box/compacted trash	up to 200 mrem/hr
1	10	50 ft ³ liners/solidified evaporator bottoms	200 - 500 mrem/hr
2	9	55 gal drum/solidified radiac waste	up to 100 mrem/hr
2	16	55 gal drum/compacted trash	0 to 1 mrem/hr
2	6	55 gal drum/compacted trash	1 to 2 mrem/hr
2	11	55 gal drum/compacted trash	2 to 5 mrem/hr
2	9	55 gal drum/compacted trash	5 - 20 mrem/hr
2	5	55 gal drum/compacted trash	20 - 100 mrem/hr
2	2	55 gal drum/compacted trash	100 - 500 mrem/hr
2	1	55 gal drum/compacted trash	500 - 1000 mrem/br
2	1	55 gal drum/compacted trash	1000 - 2000 mrem/hr
2	2	4'x4'x7' LSA boxes	0 - 1 mrem/hr
2	2	4'x4'x7' LSA boxes	1 - 2 mrem/hr
2	3	4'x4'x7' LSA boxes	2 - 10 mrem/br
2	• 3	4'x4'x7' LSA boxes	10 - 20 mrem/hr
2	3	4'x4'x7' LSA boxes	20 - 100 mrem/hr
2	1	4'x4'x7' LSA boxes	100 - 200 mrem/hr

3.0 TECHNICAL EVALUATION

This section summarizes the licensing issues which were considered in the design of the ISWSF. These issues deal with the expected performance of the facility during normal operation and various design basis events.

3.1

Licensing Issues

The licensing issues associated with the operation of the ISWSF are:

- Demonstrating compliance with 40 CFR Part 190 with respect to offsite doses.
- b. Demonstrating compliance with 10 CFR Part 20 with respect to onsite dose limits.
- c. Demonstrating that the design basis events for the facility have been properly considered. The design basis events for this facility are high winds, OBE, fire, and flooding.
- d. Demonstrating compliance with the principles of ALARA.

Each of these issues is addressed in the following

sections.

3.2 Dose Assessment

The ISWSF is designed so that during normal operation (1) the requirements of 40 CFR Part 190 are met at the site boundary and beyond, and (2) the dose rate at the outer fence is limited to 0.6 mrem/hr or less. In addition, the consequences of design basis events have been evaluated to assure that public use of areas beyond the exclusion areas is not interrupted or restricted.

This section presents the analyses that demonstrate the above objectives are met.

3.2.1 Off Site

3.2.1.1 Normal Operation

The total annual offsite dose from the site to any individual is limited to 25 mrem by 40 CFR Part 190. The nearest site boundary for the ISWSF is the normal high water mark on the east bank of the island. As applied to the site boundary, the 40 CFR Part 190 limits equate to a 0.3 mrem/hr dose rate based on a 67 hr/yr occupancy (Note 2) with an 80 percent contribution factor (80 percent of the total 25 mrem). As explained in Section 3.2.2 the dose rate at the fence inside the site boundary, and approximately 240 feet from the ISWSF, is below 0.6 mrem/hr. The dose rate at the site boundary at the normal high water line of the river will be much less than the 0.3 mrem/hr allowable, due to the shielding effect of the flood protection dike.

In addition to satisfying 40 CFR Part 190 at the site boundary an analysis was performed to determine the dose resulting from the ISWSF at the nearest residence. The dose at the nearest residence, located approximately 1550 feet ENE of the facility, was determined to be 13 mrem/yr.

A general purpose gamma ray scattering code was used to determine the annual dose from direct and scattered radiation at the nearest residence. The code used was the G-33 version of " G^3 : A General Purpose Gamma-Ray Scattering Program," described in Los Alamos Scientific Laboratory publication LA 5176, dated June 1973.

The calculation of the dose rate at the nearest residence included the following considerations:

- a. The ISWSF was assumed to contain the waste generated in six months at the monthly generation rates given in Table 2-1.
- b. The predominant radionuclide encountered in the Unit 2 containment, Cesium-137, was assumed to be the source of radiation in all waste packages.
- c. The factor of 0.7 specified in Regulatory Guide 1.109, Revision 1, was used to account for shielding and occupancy characteristics at the nearest residence.
- 3.2.1.2 Design Basis Events

Design basis events considered were high winds, an operating basis earthquake, a fire, and flooding.

3.2.1.2.1 High Winds

From the TMI-2 FSAR the design wind velocity, based on the 100-year recurrence interval, is 80 miles per hour at 30 feet above grade. A review of the waste packages in the ISWSF resulted in the determination that the only waste packages that may move when subjected to the design basis wind were the drums of compacted trash located in the open staging areas. It was determined that a single 55-gallon drum weighing less than 250 pounds might move under design wind conditions.

Note 2. Regulatory Guide 1.109, Rev. 1, Table E-5 Page 40--Recommended values for the maximum exposed individual in lieu of site-specific data.

12

2

2

2

Most drums are expected to weigh more than 250 pounds. As noted in the "Recovery Quarterly Progress Report for the Period Ending September 30, 1980," the average weight of 55-gallon drums containing compacted trash is 315 pounds. It was determined that drums weighing less than 250 pounds can be strapped together in groups of four, so that their total weight is greater than 600 pounds, thus preventing their movement under high wind conditions.

Administrative procedures will be written to assure that drums will be heavy enough to prevent their movement by design wind forces.

Although the movement of drums in the unshielded portions of the ISWSF will be precluded as noted above, an analysis of the radiological consequences of high wind conditions was made. The resulting maximum dose to the public from the postulated airborne release was less than 0.01 mrem for the inhalation pathway. The following considerations were made in this analysis:

- All drums containing compacted trash in the unshielded portions of the ISWSF were assumed to be damaged by the high wind forces.
- o The predominant radionuclide encountered in the Unit 2 containment, Cesium 137, was assumed to be the source of radiation in all waste packages. Approximately 12 curies of Cesium 137 are estimated to be contained in the drums of compacted trash in the unshielded portion of the ISWSF. Since Strontium 90 is also present in the containment, the drums were assumed to contain an additional 1.2 curies of strontium.
- A release fraction of 10-4 of the contents of the damaged drums was assumed based on extrapolation of data presented in "Environmental Survey of Transportation of Radioactive Materials to and from Nuclear Power Plants," December 1972.
- The release was assumed to occur over a one-hour period.
- o An atmospheric dilution factor of 2.4 x 10⁻⁵ sec/m³ was used, based on an 80 mile per hour wind and a distance of 1150 feet from the ISWSF to the nearest boundary of the exclusion area. Stability Class D conditions were assumed with no credit taken for building wake effect.

3.2.1.2.2 Operating Basis Earthquake (OBE)

In the event of an OBE, the ISWSF may collapse; however, the radioactive waste packages would remain in the general area of the facility. The resulting maximum dose to the public from a postulated airborne release would be less than 0.03 mrem for the inhalation pathway. The following considerations were made in this analysis:

- All drums containing compacted trash and all LSA boxes in the facility were considered as a potential source of an airborne release.
- o The estimated content of these drums and boxes was 81 and 8.1 curies of Cesium 137 and Strontium 90, respectively.
 - A release fraction of 10⁻⁶ of the contents of the drums and boxes was assumed, based on the data presented in "Environmental Survey of Transportation of Radioactive Materials to and from Nuclear Power Plants," December 1972.
 - The atmospheric dilution factor of 8.1 x 10⁻⁴ sec/m³ was used, based on a Stability Class F, 1 m/sec wind speed, and 1150 feet to the nearest boundary of the exclusion area. No credit was taken for the building wake effect.

3.2.1.2.3 Fire

A fire in the ISWSF will not result in the release of radioactive material. This is based on having all the radioactive material in sealed metal containers or fixed in place such that radionuclides cannot become airborne. In addition, the amount of combustible material, the wooden pallets and small amounts of electrical cable, exposed to an ignition source is insufficient to burn through a container. Also, based on available information regarding the contents of the waste packages, spontaneous combustion within a container will not occur.

3.2.1.2.4 Flooding

The Three Mile Island site is protected against a design flood of 1,100,000 cfs flow in the Susquehanna River. This protection is furnished by the site dike, which has a minimum elevation of 304 feet along the southern end of the island. In the event of a design flood, which is equivalent to a river level of approximately 300.5 feet, the drainage culvert gate at the southeast dike will close, isolating the site storm drain system from the river. Consequently, the TMI site design flood will have no adverse impact on the ISWSF.

In the event of a probable maximum flood (PMF), the river flow rate will slowly increase to the calculated maximum of 1,625,000 cfs. As the river level increases it will overtop the south dike. The water level on the island will then rise to a maximum PMF flood height of 308.5 feet. As noted in Figure 2.4-7 of the TMI-2 FSAR, an advance warning of at least 36 hours will precede the arrival of PMF.

3

3-4

The ISWSF is not protected against the PMF; therefore, the ISWSF will be inundated in the very unlikely event a PMF occurs. The following discussion addresses the possible offsite releases of radioactive materials that could result from submergence of radioactive waste drums and boxes.

Since the waste packages are sealed and ready for offsite shipment, they will resist water intrusion. Should the waste packages leak, releases would be minimal due to the absence of a driving force for release except for diffusion of radionuclides in water. Therefore, in light of the extremely low probability of occurrence of the PMF (recurrence interval greater than 100 years) and the expected minimal leakage into the waste packages, the design of the ISWSF regarding flooding is considered to be adequate.

3.2.2 On Site

.

The dose rates at the outer fence surrounding the ISWSF were calculated to ensure that the values are less than the 0.6 mrem/hr in accordance with 10 CFR Part 20. This was done by calculating the gamma dose rates from a planar source to a point at a given distance from the source.

The major assumptions made in the performance of this analysis were:

- a. The only contributing isotope was Cesium-137.
- All waste packages were at the maximum contact dose rate given in Table 2-1.
- c. The facility was assumed to contain the waste generated in six months, based on the generation rates given in Table 2-1.

The resulting dose at the outer fence surrounding the ISWSF is calculated to be less than 0.6 mrem/hr.

Although the dose rates at the fence have been determined to be less than 0.6 mrem/hr, this is based on the information presented in Table 2-1. In order to allow for deviations from this list, a radiation survey will be performed whenever the quantity or arrangement of packages in the ISWSF is significantly altered to ensure that the dose rate at any given point around the outer fence does not exceed 0.6 mrem/hr.

3.3 Occupational Exposures

"Use of the ISWSF will result in occupational radiation exposure to personnel. The operational and maintenance activities to be performed in the facility have been evaluated to determine the length of time workers will be exposed to a radiation environment. This information has been combined with expected radiation fields in the ISWSF to

arrive at a projected annual exposure of from 17 to 22 man-rem for this facility. Of this exposure, approximately 80 percent is attributable to radioactive waste originating in Unit 1.

3.3.1 Design Features

Several design provisions have been included in the ISWSF to minimize occupational exposures. These provisions include segregation of waste with higher radiation levels from those with lower radiation levels, use of shielding, and other provisions as noted below.

The arrangement of the ISWSF allows containers to be stored in the low radiation (unshielded) sections of the facility without entering the higher radiation (shielded) sections. The shield wall between the truck loading/unloading area reduces the dose rate in this area from the material in storage.

A roof has been provided for the facility to minimize the intrusion of rain water which must be collected and sampled prior to disposal. The sumps have been designed so that the shielded areas need not be entered to pump the sumps.

Location of the forklift truck aisles on the outside of the facility rather than using a single central aisle results in a lower radiation field at the aisle.

3.3.2 Man-Rem Estimate

The duration of activities occurring in the ISWSF was estimated by considering the number of radioactive waste packages to be placed in the facility. Factors considered in the analysis of time spent in the radiation area included the following:

- a. 55-gallon drums are handled by an unshielded forklift in groups of four drums on a single pallet. The drums are stored on the pallet.
- b. LSA boxes and the 50 ft³ containers are handled one at a time by the forklift.
- c. The speed of the forklift was assumed to be three miles per hour except when maneuvering to pick up or store a load.
- d. Approximately one-half the time the forklift is in operation it is not carrying a load. This accounts for the return trip to or from the loading/unloading area to the staging areas to pick up another load.
- Two forklift breakdowns per year in the radiation areas were assumed.

- f. Allowances for time spent in the radiation area by other than the forklift operator were made to account for the shipment vehicle driver, health physics technician, and a laborer to assist the forklift operator.
- .; g. An allowance has been made for relocating containers within the facility.

The radiation fields in which the activities in the ISWSF occurred were estimated using the number of radioactive waste packages in the facility, and the dose rate of each package. Factors considered in the determination of the radiation fields included the following:

- a. The LSA boxes were assumed to be planar sources, with the dose calculated on a perpendicular to the plane at the desired distance.
- b. For cylindrical containers, the source was modeled as an infinite cylinder and only cylindrical spreading was assumed.
- c. No credit was assumed for the shielding effect of the content of one container on an adjacent container except in the case of solidified waste in 50 ft³ liners.
- d. The ISWSF was assumed to contain a six-month inventory of containers at all times.

The area radiation levels calculated for the various areas in the ISWSF are given in Table 3-1.

The man-rem assessment combined the radiation fields described above with each of the handling, maintenance, and vehicle survey activities. The evolutions evaluated included transit of a loaded vehicle from Unit 1 or Unit 2 to the ISWSF, placing the containers in storage, removing the containers from storage to the shipment vehicle at a later point in time, and a health physics survey of the shipment vehicle.

Assuming that the man-rem exposures from the ISWSF activities control the number of workers required to conduct material handling operations, the following approximate number of personnel would be required for the operation of this facility during the year:

3-7

...

Function	Number of Workers	Dose per Worker
Health Physics Technicians	.1	.5 rem
• Forklift Operators	4	4 rem (max.)
All other functions (laborers, truck drivers, maintenance personnel)	l equivalent worker	5 rem total

3-8

•

. .

TABLE 3-1

.

AREA RADIATION LEVELS WITH SIX MONTHS DESIGN BASIS INVENTORY

4.

.

. .

Area	Radiation Level (m:em/hr)
Survey Area	0.5
Open Staging Area	
Unit 2 LSA boxes	60
Unit 2 drums	180
Unit 1 drums	180
Shielded Staging Area	
1-1	

ANTA	·				1600
		2 1 2 7 5 1			
	and the second second		and a second second	化学 计学校语言	
Unit	2				1170
	100204160-1-6				11/0

at (1941

COMPARISON WITH PROGRAMMATIC ENVIRONMENTAL IMPACT STATEMENT (PEIS)

Section 9.2.1.1 of the PEIS describes a facility for the temporary storage of certain low level radioactive wastes. The contents of the facility are given in Table 4-1. The radiation levels at the fence surrounding the facility will be less than 0.6 mrem/hr. This facility is judged in Section 9.5.1.2 of the PEIS to have negligible environmental exposures to the general population.

There are some minor differences between the ISWSF described in this report and the facility described in the PEIS. These differences are primarily in the number of containers to be stored in the ISWSF. Table 4-1 contains the design basis contents of the ISWSF. However, as shown in this report, the ISWSF will result in negligible environmental exposures to the general population.

TABLE 4-1

• *

•••••••

CONTENTS OF STAGING FACILITY

	PEIS Facility	ISWSF
55-Gallon Drums	800	810
LSA Boxes	$150 \\ (4 ft x 3 ft x 6 1/2 ft)$	90 (4 ft x 4 ft x 7 ft)
	wooden	metal
50-ft ³ Liners	60	60

5.0 SAFETY EVALUATION

10 CFR 50, paragraph 50.59, "Changes, Tests, and Experiments," permits the holder of an operating license to make changes to the facility provided the change does not involve a modification of the plant technical specifications and the change is determined not to be an unreviewed safety question. As summarized below, the operation of the ISWSF neither requires a modification to the plant technical specifications nor is it deemed to be an unreviewed safety question as defined in 10 CFR 50, paragraph 50.59.

5.1

Technical Specifications

There are no Recovery Technical Specifications regarding the storage of solid or solidified radioactive waste. The proposed change does not require any additional technical specifications in order to satisfy the licensing basis of the plant. Therefore, the operation of the ISWSF does not require changes to the existing technical specifications.

5.2 Unreviewed Safety Question

The operation of the ISWSF will not increase the probability of occurrence or the consequences of an accident or malfunction of equipment important to safety previously evaluated in the safety analysis report. This is based on the location of the facility being such that there is no interface with existing safety-related equipment or structures.

The possibility of an accident or malfunction of a different type than any evaluated previously in the safety analysis report will not be created by the operation of the ISWSF. This is due to the passive nature of the facility and the fact that all the radioactive waste is in either a solid/solidified or fixed form.

As stated in Section 5.1, the operation of the ISWSF will not result in a reduction in the margin of safety as defined in the basis for any technical specification.

Based on the above, the operation of the ISWSF is deemed not to be an unreviewed safety question as defined in 10 CFR 50, paragraph 50.59.