

DISTRIBUTION:
 Docket No. 50-320
 NRC PDR
 Local PDR
 TMIPO HQ r/f
 TMI Site r/f
 TERA
 LBarrett
 RBellamy
 AFasano
 JWiebe
 Attorney, ELD
 IE
 ACRS
 BSnyder
 RWeller
 TBarnhart
 TPOindexter

AUG 18 1982

NRC/TMI-82-047

Docket No. 50-320

Mr. Bahman Kanga
 Director, TMI-2
 GPU Nuclear Corporation
 P.O. Box 480
 Middletown, PA 17057

Dear Mr. Barton:

Subject: Recovery Operations Plan Change No. 15 (Recovery Operations Plan Change Request No. 12)

- References: (a) Letter from J.J. Barton to L.H. Barrett, same subject, dated April 21, 1982, 4400-82-L-0052.
 (b) Letter from J.J. Barton to L.H. Barrett, same subject, dated July 2, 1982, 4400-82-L-0087.

The Nuclear Regulatory Commission Staff has reviewed your Recovery Operations Plan Change Request No. 12 forwarded in reference (a) and your amended Recovery Operations Plan Change Request No. 12 forwarded in reference (b). The change contains, in part, various editorial changes in the sections concerning the Control Room Emergency Air Cleanup System, the Fuel Handling Building Air Cleanup System, and the Auxiliary Building Air Cleanup System. In addition, the change revises the surveillance requirements for the above systems to more nearly reflect actual system requirements, updates references to the most recently issued ANSI Standards and, in general, clarifies the surveillance requirements.

The staff approves your change request since the changes do not represent a reduction in safety and in some cases more stringent requirements are imposed to insure the systems are operating properly. In addition, the clarification of the requirements will allow less chance for misinterpreting the requirements which also enhances safety.

We therefore, are enclosing the amended sections (ROP Change No. 15) to the Plan.

original signed by

Lake H. Barrett
 Deputy Program Director
 TMI Program Office

Enclosure: As stated

cc: J. Barton
 J. Larson
 L. King

OFFICE	Service Distribution List	TMIPO	TMIPO	TMIPO
SURNAME	B209230133 B20818	Wiebe:js	RBellamy	LBarrett
DATE	PDR ADOCK 05000320	8/13/82	8/1/82	8/18/82
	PDR			

SERVICE DISTRIBUTION LIST

Ronald C. Haynes
Regional Administrator, Region I
U.S. Nuclear Regulatory Commission
531 Park Ave.
King of Prussia, PA 19406

John F. Wolf, Esq., Chairman,
Administrative Judge
3409 Shepherd Street
Chevy Chase, MD 20015

Dr. Oscar M. Paris
Administrative Judge
Atomic Safety and Licensing Board Panel
U.S. Nuclear Regulatory Commission
Washington, DC 20555

Mr. Frederick J. Shon
Administrative Judge
Atomic Safety and Licensing Board Panel
U.S. Nuclear Regulatory Commission
Washington, DC 20555

Karin W. Carter
Assistant Attorney General
505 Executive House
P.O. Box 2357
Harrisburg, PA 17120

Dr. Judith H. Johnsrud
Environmental Coalition
on Nuclear Power
433 Orlando Avenue
State College, PA 16801

George F. Trowbridge, Esq.
Shaw, Pittman, Potts and
Trowbridge
1800 M Street, NW
Washington, DC 20036

Atomic Safety and Licensing
Board Panel
U.S. Nuclear Regulatory Commission
Washington, DC 20555

Atomic Safety and Licensing
Appeal Panel
U.S. Nuclear Regulatory Commission
Washington, DC 20555

Secretary
U.S. Nuclear Regulatory Commission
ATTN: Chief
Docketing & Service Branch
Washington, DC 20555

Mr. Larry Hochendoner
Dauphin County Commissioner
P.O. Box 1295
Harrisburg, PA 17108-1295

John E. Minnich, Chairperson
Dauphin County Board of Commissioners
Dauphin County Courthouse
Front and Market Streets
Harrisburg, PA 17101

Dauphin County Office of Emergency
Preparedness
Court House, Room 7
Front & Market Streets
Harrisburg, PA 17101

U.S. Environmental Protection Agency
Region III Office
ATTN: EIS Coordinator
Curtis Building (Sixth Floor)-
6th and Walnut Streets
Philadelphia, PA 19106

Thomas M. Gerusky, Director
Bureau of Radiation Protection
Department of Environmental Resources
P.O. Box 2063
Harrisburg, PA 17120

David Hess
Office of Environmental Planning
Department of Environmental Resources
P.O. Box 2063
Harrisburg, PA 17120

Willis Bixby, Site Manager
U.S. Department of Energy
P.O. Box 88
Middletown, PA 17057-0311

Herbert Feinroth, Acting Deputy
Director of Coordination and
Special Projects, NE-550
U.S. Dept. of Energy
Washington, DC 20545

William Lochstet
104 Davey Laboratory
Pennsylvania State University
University Park, PA 16802

Randy Myers, Editorial
The Patriot
812 Market Street
Harrisburg, PA 17105

Robert B. Borsum
Babcock & Wilcox
Nuclear Power Generation Division
Suite 220
7910 Woodmont Ave.
Bethesda, MD 20814

Judith A. Dorsey
1315 Walnut Street
Suite 1632
Philadelphia, PA 19107

Linda W. Little
5000 Hermitage Drive
Raleigh, NC 27612

Marvin I. Lewis
6504 Bradford Terrace
Philadelphia, PA 19149

Jane Lee
183 Valley Road
Etters, PA 17319

J. B. Liberman, Esquire
Berliack, Israels, Liberman
26 Broadway
New York, NY 10004

Walter W. Cohen, Consumer Advocate
Department of Justice
Strawberry Square, 14th Floor
Harrisburg, PA 17127

Edward O. Swartz
Board of Supervisors
Londonderry Township
RFD #1 Geyers Church Road
Middletown, PA 17057

Robert L. Knupp, Esquire
Assistant Solicitor
Knupp and Andrews
P.O. Box P
407 N. Front Street
Harrisburg, PA 17108

Robert Q. Pollard
Chesapeake Energy Alliance
609 Montpelier Street
Baltimore, MD 21218

John Levin, Esquire
Pennsylvania Public Utilities
Commission
P.O. Box 3265
Harrisburg, PA 17120
Honorable Mark Cohen
512 E-E Main Capital Building
Harrisburg, PA 17120

SURVEILLANCE REQUIREMENTS

4.7.6.1.3 A Special Report shall be prepared and submitted to the Commission within 10 days if evidence of degradation is noted during an inspection. This report shall describe the extent and nature of the degradation and the plans and schedule for restoring the dike and erosion protection to a status equivalent to the original design provisions.

4.7.7 CONTROL ROOM EMERGENCY AIR CLEANUP SYSTEM

4.7.7.1 The Control Room Emergency Air Cleanup System shall be demonstrated OPERABLE:

- a. At least once per 12 hours by verifying that the control room air temperature is less than or equal to 100°F.
- b. At least once per 31 days by initiating, from the control room, flow through the HEPA filters and charcoal adsorbers and verifying that the system operates for at least 15 minutes; and the pressure drop across the combined HEPA filters and charcoal adsorbers banks is less than six (6) inches water gauge while operating.
- c. At least once per 18 months or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) following painting, fire or chemical release in any ventilation zone communicating with the system by:
 1. Verifying that the cleanup system satisfies the in-place testing acceptance criteria and uses the test procedures of Regulatory Positions C.5.a, C.5.c* and C.5.d* of Regulatory Guide 1.52, Revision 2, March 1978, and the system flow rate is 14,350 cfm \pm 10%.
 2. Verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Guide 1.52, Revision 2, March 1978, when performing Methyl Iodide, 30°C, 95% RH testing per Table 5-1 of ANSI N509-1980 meets an acceptable criteria of 5% penetration maximum.
 3. Verifying a system flow rate of 14,350 cfm + 10% during system operation when tested in accordance with ANSI N510-1980, Section 8.3.1 Paragraphs 3 and 4.
- d. After every 720 hours of charcoal adsorber operation by verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, when performing Methyl Iodide, 30°C, 95% RH testing per Table 5-1 of ANSI N509-1980 meets an acceptance criteria of 5% penetration maximum.

*The prerequisites of Section 10.3 and 12.3 of ANSI-N510-1980 do not apply.

8209230136 820818
PDR ADOCK 05000320
P PDR

SURVEILLANCE REQUIREMENTS

CONTROL ROOM EMERGENCY AIR CLEANUP SYSTEM (Continued)

- e. At least once per 18 months by:
1. Verifying that the pressure drop across the combined HEPA filter and charcoal adsorber banks is less than 6 inches water gauge while operating the system at a flow rate of 14,350 cfm \pm 10%.
 2. Verifying that on a control room air inlet radiation test signal or chlorine detection test signal, the system automatically switches into a recirculation mode of operation with flow through the HEPA filters and charcoal adsorber banks.
 3. Verifying that the system maintains the control room at a positive pressure of greater than or equal to 1/10 inch water gauge relative to the outside atmosphere during system operation.
- f. After each complete or partial replacement of a HEPA filter bank by verifying that the HEPA filter banks remove greater than or equal to 99.95% of the DOP when they are tested in-place in accordance with ANSI N510-1980* Section 10 while operating the system at a flow rate of 14,350 cfm \pm 10%.
- g. After each complete or partial replacement of a charcoal adsorber bank by verifying that the charcoal adsorbers remove greater than or equal to 99.95% of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1980,* Section 12, while operating the system at a flow rate of 14,350 cfm \pm 10%.

*The prerequisites of Section 10.3 and 12.3 of ANSI-510-1980 do not apply.

SURVEILLANCE REQUIREMENTS

4.9 LIQUID RADWASTE STORAGE

FUEL HANDLING BUILDING/AUXILIARY BUILDING AIR CLEANUP SYSTEMS

4.9.12.1 The Fuel Handling Building Air Cleanup Exhaust System shall be demonstrated OPERABLE:

- a. At least once per 31 days by verifying that the Air Cleanup Exhaust System in the normal operating mode meets the following conditions:
 1. Exhaust Flow Rate: With two filter trains and two exhaust fans in operation in the Fuel Handling Building flow rate shall be within the 36,000 cfm to 54,000 cfm operating band.
 2. Filter Pressure Drop: While operating within the flow rate specified in 4.9.12.1.a.1 above, the d/p across the combined HEPA filters and charcoal adsorbers shall not exceed 6 inches water gauge.
 3. Fuel Handling Building Pressure: Demonstrate that the system is capable of achieving a negative pressure within the building equal to or greater (more negative) than 1/8 inch water gauge with respect to atmospheric. It may be necessary to close doors and other building openings to achieve the required value.
- b. At least once per 18 months by verifying that the ventilation system meets the following conditions:
 1. Visually inspect each filter train and associated components in accordance with Section 5 of ANSI N510-1980, as required by Regulatory Position C.5.a of Regulatory Guide 1.52, Revision 2, March 1978. The inspection should be performed prior to the flow and DOP tests of this section.
 2. Flow Test: Exhaust flow rate shall be within 18,000 cfm to 27,000 cfm operating band for each filter train with one filter train and one exhaust fan operating. Testing shall be in accordance with ANSI N510-1980, Section 8.3.1, Paragraphs 3 and 4.
 3. DOP Test: Each filter train shall be tested in accordance with Section 10 of ANSI N510-1980, as required by Regulatory Position C.5.c of Regulatory Guide 1.52, Revision 2, March 1978. Flow through the filter train being tested shall be as prescribed for the flow test in Section 4.9.12.1.b.2 above.

NOTE: Installed system flow instrumentation is adequate for the test described in 4.9.12.1.b.3 above.

SURVEILLANCE REQUIREMENTS

4. Fuel Handling Building Pressure: Demonstrate that the system is capable of achieving a negative pressure within the building equal to or greater (more negative) than 1/8 inch water gauge with respect to atmospheric. It may be necessary to close doors and other building openings to achieve the required value. A test instrument, such as an inclined manometer or equivalent, shall be used in the performance of this test.
- c. After structural maintenance of the HEPA filter or charcoal adsorber housings, or following fire or chemical release in any ventilation zone communicating with the system by verifying that the ventilation system meets the following conditions:
 1. Flow Test: Reverify exhaust flow rate for the affected filter train(s) per Section 4.9.12.1.b.2.
 2. Filter Pressure Drop: Reverify the filter pressure drop surveillance prescribed in Section 4.9.12.1.a.2 for the affected filter train(s)
 3. DOP Test: Each affected filter train shall be retested in accordance with Section 4.9.12.1.b.3.
- d. After each complete or partial replacement of a HEPA filter bank by verifying that the ventilation system meets the following conditions:
 1. DOP Test: Each affected filter train shall be retested in accordance with Section 4.9.12.1.b.3.

NOTE: Supply fans may be operated as desired except that the number of operating supply fans shall not exceed the number of operating exhaust fans.

4.9.12.2 The Auxiliary Building Air Cleanup Exhaust System shall be demonstrated OPERABLE:

- a. At least once per 31 days by verifying that the air cleanup exhaust system in the normal operating mode meets the following conditions:
 1. Exhaust Flow Rate: With two filter trains and two exhaust fans in operation in the Auxiliary building flow rate shall be within the 54,000 cfm to 80,000 cfm operating band.
 2. Filter Pressure Drop: While operating within the flow rate specified in 4.9.12.2.a.1 above, the d/p across the combined HEPA filters and charcoal adsorbers shall not exceed 6 inches water gauge.

SURVEILLANCE REQUIREMENTS

3. **Auxiliary Building Pressure:** Demonstrate that the system is capable of achieving negative pressure within the building equal to or greater (more negative) than 1/8 inch water gauge with respect to atmospheric. It may be necessary to close doors and other building openings to achieve the required value.
- b. At least once per 18 months by verifying that the ventilation system meets the following conditions:
1. Visually inspect each filter train and associated components in accordance with Section 5 of ANSI N510-1980, as required by Regulatory Position C.5.a of Regulatory Guide 1.52, Revision 2, March 1978. The inspection should be performed prior to the flow and DOP tests of this section.
 2. **Flow Test:** Exhaust flow rate shall be within 27,000 cfm to 40,000 cfm operating band for each filter train with one filter train and one exhaust fan operating. Testing shall be in accordance with ANSI N510-1980, Section 8.3.1, Paragraphs 3 and 4.
 3. **DOP Test:** Each filter train shall be tested in accordance with Section 10 of ANSI N510-1980, as required by Regulatory Position C.5.c of Regulatory Guide 1.52, Revision 2, March 1978. Flow through the filter train being tested shall be as prescribed for the flow test in Section 4.9.12.2.b.2 above.

NOTE: Installed system flow instrumentation is adequate for the test described in 4.9.12.2.b.3. above.

4. **Auxiliary Building Pressure:** Demonstrate that the system is capable of achieving a negative pressure within the building equal to or greater (more negative) than 1/8 inch water gauge with respect to atmospheric. It may be necessary to close doors and other building openings to achieve the required value. A test instrument, such as an inclined manometer or equivalent, shall be used in the performance of this test.
- c. After structural maintenance of the HEPA filter or charcoal adsorber housing, or following fire or chemical release in any ventilation zone communicating with the system by verifying that the ventilation system meets the following conditions:
1. **Flow Test:** Reverify exhaust flow rate for the affected filter train(s) per Section 4.9.12.2.b.2.
 2. **Filter Pressure Drop:** Reverify the filter pressure drop surveillance prescribed in Section 4.9.12.2.a.2 for the affected filter train(s).

SURVEILLANCE REQUIREMENTS

3. DOP Test: Each affected filter train shall be retested in accordance with Section 4.9.12.2.b.3.
- d. After each complete or partial replacement of a HEPA filter bank by verifying that the ventilation system meets the following conditions:
 1. DOP Test: Each affected filter train shall be retested in accordance with Section 4.9.12.2.b.3.

NOTE: Supply fans may be operated as desired except that the number of operating supply fans shall not exceed the number of operating exhaust fans.