


2/

**MASTER**

**GEND-INF- 017**

**Volume II  
November 1981**



This is an informal report intended for use as a preliminary or working document

**GEND**

General Public Utilities • Electric Power Research Institute • U.S. Nuclear Regulatory Commission • U.S. Department of Energy

## **FIELD MEASUREMENTS AND INTERPRETATION OF TMI-2 INSTRUMENTATION: CF-1-PT43**

**J. E. Jones  
J. G. Smith  
M. V. Mathis**

**Prepared for the  
U.S. Department of Energy  
Three Mile Island Operations Office  
Under DOE Contract No. DE-AC07-78DO1570**

**DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED**

**DISCLAIMER**

This document contains information that is the property of the U.S. Government and is loaned to you for your information only. It is not to be distributed outside your organization. It is to be destroyed when it is no longer needed. It is not to be used for any purpose other than that for which it was prepared. It is not to be used to support any position or to criticize any person or organization. It is not to be used to support any position or to criticize any person or organization.

# **FIELD MEASUREMENTS AND INTERPRETATION OF TMI-2 INSTRUMENTATION: CF-1-PT4**

**J. E. Jones**  
**J. G. Smith**  
**M. V. Mathis**

**Technology for Energy Corporation/  
General Public Utilities Nuclear Corporation**

**November 1981**

**Published on Behalf of the GEND Group  
by  
EG&G Idaho, Inc.  
Idaho Falls, Idaho 83415**

**Prepared for the  
U.S. Department of Energy  
Three Mile Island Operations Office  
Under DOE Contract No. DE-AC07-76ID01570**

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1. INTRODUCTION	1-1
2. INSTRUMENT LOCATION, CABLING, AND TERMINATIONS	2-1
3. MEASUREMENT PROCEDURES	3-1
4. MEASUREMENTS	4-1
5. INTERPRETATION OF MEASUREMENTS	5-1
6. CONCLUSIONS	6-1
APPENDIX	

## LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
2-1 CF-1-PT3 Composite Electrical Diagram	2-2
2-2 Foxboro Model E11GM Design	2-4
4-1 Current-to-Voltage Test Fixture	4-2
4-2 Oscilloscope Traces of Pressure Signal	4-3
4-3 High Frequency Spectrum of Pressure Signal	4-4
4-4 Low Frequency Spectra of Pressure Signal	4-5
4-5 TDR Trace of Pressure Signal Lines	4-8
4-6 TDR Trace of (+) Signal to Shield	4-9
4-7 TDR Trace of (-) Signal to Shield	4-10

## LIST OF TABLES

<u>Table</u>	<u>Page</u>
2-1 Termination Points for CF-1-PT3 Measurements	2-3
4-1 Capacitance, Impedance, and Resistance Measurements	4-7
5-1 Major AC Components on the Pressure Signal	5-2
5-2 Summary of TDR Measurements	5-4

## Section 1

### INTRODUCTION

During and following the TMI-2 accident, a number of instruments failed or were suspected of providing erroneous readings. Because of this problem, industry concerns were focused upon the behavior of instrumentation under adverse conditions. To better understand failure mechanisms, the Technical Integration Office (TIO) contracted Technology for Energy Corporation (TEC) to perform field measurements on a set of selected TMI-2 instruments to determine in-situ operating characteristics. For some instruments, these measurements were to be performed prior to removal (and replacement with new instruments) in order to have a cross reference with post removal observations. For other instruments an indication of the condition of the instrument (i.e., fully operational or failed) was desired.

This report describes the measurements and results on the Core Flood Tank 1B pressure monitor CF-1-PT3. This instrument consists of a Foxboro Model EIIGM-HSAE1 electronic absolute pressure transmitter connected to a readout module by approximately 600 feet of cable through a penetration and an instrument mounting terminal block. This instrument was one of the few primary loop pressure monitors that was believed not failed during the accident. As a result, measurements on this instrument were performed to determine if it was properly functioning or if it had suffered some degradation.

## Section 2

### INSTRUMENT LOCATION, CABLING, AND TERMINATIONS

A review of appropriate drawings from Foxboro and Burns & Roe (itemized in the Appendix in the measurement procedure, page A-5 and A-6) resulted in the composite electrical diagram shown in Figure 2-1. From this information, a list of the appropriate termination points for performing measurements in Control Cabinet 150 was generated and is given in Table 2-1. Figure 2-1 also indicates the cable lengths pulled during instrument installation and lengths after trimming between each termination and/or junction point.

The pressure sensing assembly is a Foxboro Model EIIGM-HSAE1 which is shown in a cross-sectional view in Figure 2-2. This instrument has a normal range of 0-750 psia producing a 10-50 ma current output. The electrical diagram of the detector circuit is also shown in Figure 2-2.

Since measurements were being made in Control Cabinet 150, the effect of the readout meter (attached to the signal line) was also present on the observed instrument response. However, since this readout was located outside containment, it did not experience severe operating environments and thus was not considered to have failed.




Figure 2-1. CF-1-PT3 Composite Electrical Diagram.



2-3

Table 2-1

TERMINATION POINTS FOR CF-1-PT3 MEASUREMENTS

Signal	Cabinet 150 Identification*
+Signal	TB2-9-4/4
-Signal	TB2-9-4/5
Shield	TB2-9-4/3

\*From cable IT1720I

**Figure 2-2. Foxboro Model E11GM Design.**

### Section 3

#### MEASUREMENT PROCEDURES

As a result of generating the composite electrical diagram and from a review of the Foxboro EIIA Series Electronic Absolute Pressure Transmitters technical information literature, measurements to be performed were identified as:

1. Determine as-found condition of pressure indication and record signal output
2. Perform passive measurements (i.e., passively monitor signals) on each electrical connection consisting of time domain waveforms, very-high frequency spectrum analysis (i.e., MHz region), and frequency spectra below 100 kHz
3. Perform resistance, capacitance, impedance, and Time Domain Reflectometry (TDR) active measurements (i.e., actively introducing a test signal).

These measurements were designed to verify the operation of the Readout Module and the power supplies, but the focus of the measurement was on the pressure sensing assembly, cabling, and terminations/connections to the assembly. The Appendix contains the detailed procedure which was followed during the measurement program, and a summary of measurements is presented in the next section.


## Section 4

### MEASUREMENTS

Since the pressure signal from CF-1-PT3 was a 10-50 ma current loop, a test fixture was needed to convert this current to voltage for field measurements. A sketch of the test fixture used for this conversion is given in Figure 4-1. However, before insertion of the test fixture into the circuit, the readout of CF-1-PT3 was recorded as 162 psi to insure that the fixture did not affect the device. Following the test fixture insertion, the readout was 170 psi. This difference was probably due to operator interpretation of the meter and was not believed to have been the effect of the fixture because the signal increased rather than decreased with the added load.

After the insertion of the test fixture and verification of CF-1-PT3 output reading, the 1-5 volt signal from the connections on the test fixture was recorded for approximately 10 minutes on a FM recorder. During this recording, the DC voltage was measured (with a Keithley Model 177 DVM) as 1.89 volts, or equivalently 18.9 ma current.

The next measurement consisted of photographing the output waveform from the screen of a storage oscilloscope. Figure 4-2 shows the results of these time trace measurements for two different time scales. Along with the time traces, both high and low frequency spectra (frequency domain) were taken of the signal. Figure 4-3 shows the measured spectrum over a 4 MHz bandwidth, while Figure 4-4 shows spectra over both 100 kHz and 1 kHz ranges.



\*Note: 100 ohm resistance converts 10-50 ma range to 1-5 volts for testing.

Figure 4-1. Current-to-Voltage Test Fixture.




Photo 112-1

Time - 20 $\mu$ sec/div

Gain - 20 mV/div




Photo 112-2

Time - 5msec/div

Gain - 20 mV/div

Figure 4-2. Oscilloscope Traces of Pressure Signal.





Photo 112-3

BW - 3 KHz


Scan width - 0.5 MHz/div

Scan time - 1sec/div

Figure 4-3. High Frequency Spectrum of Pressure Signal.



a) Photo 112-4  
100 KHz Range  
+20 db Reference



b) Photo 112-5  
1 KHz Range  
+20 db Reference

Figure 4-4. Low Frequency Spectra of Pressure Signal.



Following the frequency spectra measurements, electrical calibration was performed on the CF-1-PT3 readout module by a TMI technician. No significant adjustments were noted during this calibration. After electrical calibration, power was removed from CF-1-PT3. The test fixture was removed and all signal lines between cable IT1720I and cabinet 150 were disconnected.

A series of active measurements (i.e., actively introducing a test signal into the circuit) was then performed. Table 4-1 shows the results of capacitance, impedance, and DC resistance measurements on the field cable lines. A set of TDR measurements were taken on the signal lines to determine possible cable defects. The resulting TDR traces are shown in Figures 4-5 to 4-7.

Table 4-1


## CAPACITANCE, IMPEDANCE, AND RESISTANCE MEASUREMENTS

Signal	<u>Capacitance (nF)</u>			<u>Impedance (ohms)</u>			Resistance
	100Hz	1kHz	100kHz	100Hz	1kHz	100kHz	
+Signal -Signal	3.5	3.3	-312	182K	46K	5.3	0F <sup>†</sup>
+Signal Shield	-- <sup>*</sup>	28	37	--	6K	43	0F
-Signal Shield	--	18	34	--	6K	44	0F

\* Indicates data was erratic.

<sup>†</sup> Indicates overflow, i.e., above  $20 \times 10^6$  ohms.

STRIP CHART 112-1



Setting - 500 $\mu$ p/div

Range - 52.6 ft/div


Sensitivity - 0.25

Filter - 5 Hz

Cable dielectric - other

Figure 4-5. TDR Trace of Pressure Signal Lines.

STRIP CHART 112-2

Setting - 500 $\mu$ o/div

Range - 52.6 ft/div


Sensitivity - 0.25

Filter - 5 Hz

Cable dielectric - other

Figure 4-6. TDR Trace of (+) Signal to Shield.

STRIP CHART 112-3



Setting -  $500\mu\text{p}/\text{div}$

Range - 52.6 ft/div

Sensitivity - 0.25 V/div

Filter - 5 Hz

Cable dielectric - other

Figure 4-7. TDR Trace of (-) Signal to Shield.

## Section 5

### INTERPRETATION OF MEASUREMENTS

This section presents a summary of the interpretation of the measurements taken on CF-1-PT3. This interpretation is intended to indicate the condition of the device based on observed data.

Since this device varies from 10-40 ma for a 750 psi pressure range, the observation of 170 psi readout indicates that the current should be 19.07 ma. The measured current of 18.9 ma (1.89 volts across 100 ohms) matches within 1% of this expected value, which indicates the readout meter is correctly calibrated.

The time traces and frequency spectra do not indicate any serious contamination which would affect the DC readout. Table 5-1 lists the low level AC components present on the pressure signal. Note that even though up to 1.4 ma P-P fluctuations are present, readout devices normally respond at low frequencies. As a result, the worst-case effect of these AC variations is likely to be less than the 0.017 ma RMS value given for the 60 Hz components.

The capacitance, impedance, and resistance data given in Table 4-1 is difficult to quantitatively interpret, but qualitative results are possible. The data indicates very low effective capacitance values, which would be expected from the amplifier section of the current loop driver. Other characteristics expected from the amplifier are extremely high DC resistance values and decreasing impedance at higher frequencies. Since all expected phenomena are present, there is

5-2

Table 5-1

MAJOR AC COMPONENTS ON THE PRESSURE SIGNAL

Frequency	Amplitude
60 Hz and harmonics	1.7 mV RMS (0.017 ma RMS)
16 kHz	70 mV P-P (0.7 ma P-P)
16 kHz and harmonics	20 mV RMS (0.2 ma RMS)
800 kHz	<1 mV RMS (<0.01 ma RMS)
Total Spectrum	140 mV P-P (1.4 ma P-P)

no obvious indication of instrumentation degradation from these measurements.

The results of TDR measurements performed on the cable (shown in Figures 4-5 to 4-7) are summarized in Table 5-2. Note that the lengths identified in the table are only approximate since no calibration of the cable resistance or insulation type was performed on the TDR instrument. As in other measurements, no indication of cabling problems is present in this data.



Table 5-2

## SUMMARY OF TDR MEASUREMENTS

Signal Lines	Distance* (ft)	Description**	Probable Cause
+Signal	221	Point R increase	Penetration R607
-Signal	452	Point R small decrease	Terminal block
	526	Large R increase	Electronics
+Signal	221	Point R increase	Penetration R607
Shield	452	Point R small increase	Terminal block
	505	Large R increase	Electronics
-Signal	221	Point R increase	Penetration R607
Shield	442	Point R small increase	Terminal block
	495	Large R increase	Electronics

Note: Distances are not calibrated due to lack of prior information on the cable type which prevented calibration tests.

\* TDR to terminal block test cable (15 ft) not included in distance.

\*\* R is the abbreviation for resistance.

## Section 6

### CONCLUSIONS

Based on the measurements, data reduction, and circuit analysis of CF-1-PT3, there is no indication of degradation of the instrument. The only abnormal contamination present in the pressure signal was the 16 kHz component. However, the amplitude of this signal was relatively low and, from other measurements performed at TMI, such a low-level 16 kHz component appears to be present on several unrelated instrument lines. Thus, this component is probably due to some common cause throughout the plant and is not a problem as long as the readout device properly discriminates against such high frequencies. In addition, the readout of another pressure monitor (CF-1-PT4) was noted to agree with the reading taken from CF-1-PT3. Checking the transmitter current output also produced the same current indication. Therefore, it appears that CF-1-PT3 is operational and probably calibrated since an independent monitor is producing the same output.

## UNIT 2

RECOMMENDED  
PRIORITY

CAUSE OF  
MALFUNCTION  
(IF KNOWN)

ORIGINATOR'S EMP NO. 06175 ORIGINATOR'S SIGNATURE [Signature] DATE 9-5/80  
 SUPERVISOR'S EMP NO. 06175 SUPERVISOR'S SIGNATURE [Signature] DATE 9-4/80  
 Doc/EC/G Project

RESP. LOCATION:	
CR CONTRACTOR	
20364	

*Performing Proposed Construction*  
 ORIGINATOR — SUPERVISOR — SUPERVISOR OF MAINTENANCE — MAINTENANCE FOREMAN —  
 JOB PERFORMER — MAINTENANCE FOREMAN — SUPERVISOR OF MAINTENANCE

**COPY 1**

JOB TICKET WORK REQUEST)  
REVIEW - CLASS Page A-2 RING CONTROL FORM

JOB TICKET NUMBER C 5730

1. Does work represent a change or modification to an existing system or component? If yes, an approved change modification is required per AP 1021.

C/M No. NA

Yes \_\_\_\_\_ No ✓

- 2a. Does work requires an RWP?

Yes \_\_\_\_\_ No ✓

- 2b. Is an approved procedure required to minimize personnel exposure?

Yes \_\_\_\_\_ No ✓

- 3a. Is work on a QC component as defined in GP 1008?

Yes \_\_\_\_\_ No ✓

- 3b. If 3a is yes does work have an effect on Nuclear Safety? If 3b is yes, PORC reviewed Superintendent approved procedure must be used.

Yes \_\_\_\_\_ No ✓

4. Agreement that a PORC reviewed, Superintendent approved procedure is not required for this work because it has no effect on nuclear safety. (Applies only if 3a is Yes and 3b is No).

NA

DATE

DATE

- 5a. Is the system on the Environmental Impact list in AP 1026?

Yes \_\_\_\_\_ No ✓

- 5b. If 5a is YES, is an approved procedure required to limit environmental impact?

Yes \_\_\_\_\_ No ✓

6. Agreement that 5b is No. (Required only if 5a is Yes).

NA

DATE

DATE

7. Plant status or prerequisite conditions required for work. (Operating and/or shutdown)

8. QC Dept. review, if required in item No. 3.

NA

DATE

DATE

9. Does work require code inspector to be notified?

Yes \_\_\_\_\_ No ✓

10. Supervisor of Maintenance approval to commence work

Date 7/25/80

11. Maintenance Foreman Assigned B Gilbert

12. Code Inspector Notified Name \_\_\_\_\_

Date \_\_\_\_\_

13. Shift Foreman's approval to commence work B Gilbert

Date 7/25/80

Initial if Shift Foreman signature is not required

**WORK REQUEST PROCEDURE**  
TMI Nuclear Station  
Maintenance      Page A-3      and Approval

Unit No. 2

This form outlines the format and acts as a cover sheet for a maintenance procedure. Due to the limited size of the form, additional pages may be attached as required. Work Request procedure AP 1016 Section 6 should be used as a guide in preparing the maintenance procedure.

1. Procedure Title & No.:

Sensor/Cable measurements of CF-1-PT3  
Core Fluid Tank IB Pressure String

2. Purpose: To determine signal characteristics of instrument string as it exists in plant.

3. Description of system or component to be worked on.

CF-1-PT3 Instrument String.

4. References:

See Attached

5. Special Tools, and Materials required.

See Attached

6. Detailed Procedure (attach additional pages as required)

See Attached

Supervisor of Maintenance recommends approval

Date

9/25/80

• PORC RECOMMENDS APPROVAL

Unit No. 1 Chairman

Date

Unit No. 2 Chairman

Date

• UNIT SUPERINTENDENT APPROVAL

Unit No. 1

Date

Unit No. 2


Date

• Standing Procedure

Supervisor of QC

Date

\*Note These approvals required only on Nuclear Safety Related Radiation work permit jobs

 <b>Technology for Energy Corporation</b>	<b>TITLE</b> IN-SITU MEASUREMENTS OF CABLES AND SIGNALS FROM CORE FLOOD TANK 1B PRESSURE CF-1-PT3	<b>NO.</b> TP-112
	Page A-4 <b>APPROVED</b>	<b>REV.</b> 0
<b>PROCEDURE</b>	M.V. Mathis, Director, Tech. Serv. Div.	<b>DATE</b> 9-22-80

**PURPOSE:** The purpose of these measurements is to gather baseline data and information in preparation for removal of the Core Flood Tank 1B Pressure CF-1-PT3 from the Reactor Building TMI Unit 2. The tests specified in this procedure are designed to assess the condition of the in-containment transmitter associated cabling, and readout devices. This assessment will require the use of Time Domain Reflectometry (TDR), Impedance (Z), Spectral Analysis (frequency domain), and general oscilloscope observations (with recording) of waveforms from/to the unit under test (UUT).

**PROCEDURE (ADMINISTRATIVE):**

**A. Limitations and Precautions**

1. **Nuclear Safety.** The unit is a part of the engineered reactor safeguards system and is nuclear safety-related.
2. **Environmental Safety.** Core Flood Tank 1B Pressure CF-1-PT3 can be taken out-of and restored to services without producing a hazard to the environment.
3. **Personnel Safety.** The test described herein produces no additional personnel safety hazards other than normally associated with performing instrument testing.
4. **Equipment Protection.** In the performance of each test described herein, care will be taken to insure adequate equipment protection as follows:
  - a. In all cases actual test hookups to the Unit-2 instrumentation shall be made and verified by Instrumentation Personnel.
  - b. All passive measurements (Spectral Analysis and Oscilloscope observations) of waveforms and signals from powered instruments shall be performed using high input impedance probes or inputs ( $Z \geq 1$  Meg ohm) to prevent loading of signals.
  - c. In all Time Domain Reflectometry and Impedance measurements, power will be removed from the unit under test and low level test signals prescribed in Table 4-1 shall be utilized to perform cable integrity measurements on the appropriate instrumentation cables by inserting test signals on appropriate conductors of Cable IT17201. Terminations shall be removed and replaced on TB 2-9-4 of Cabinet 150.

TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT3

NO.

TP-112

REV.

0

Page A-5

Table 4-1 Active Measurements

Active Signal Parameter	Time Domain Reflectometry	Impedance
Voltage	225 mV nominal (into 50 ohm base)	$\leq 5V$ rms
Frequency	---	100Hz, 1kHz, 10kHz, 100kHz
Current	$\leq 10mA$	$\leq 100mA$
Other	225mV, 110 picosecond pulses	---

d. In the calibration verification measurements section, baseline data on the as-found condition will be recorded prior to the performance of any adjustments or electronic calibrations.

#### B. Prerequisites

1. The Shift Supervisor/Shift Foreman shall be notified for concurrence prior to the performance of those measurements.
2. Instrumentation personnel shall be assigned to assist in the performance of these measurements.
3. All measurements and test instrumentation shall be in current calibration (traceable to NBS).
4. The Shift Supervisor/Shift Foreman shall be notified prior to starting and upon completion of the measurements.

#### C. Procedure for Performing Measurements

##### References:

1. Burns & Roe Dwg. 3024, Sh. 20.
2. Service Manual for Foxboro Series E10 Force-Balance Transmitter.
3. Burns & Roe Dwg. 3304, Sh. 24.
4. Burns & Roe Dwg. I.C. 3343, Sh. 4.

**TEC**

**TITLE**

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT3

**NO.** TP-112

**REV.** 0

Page A-6

5. Burns & Roe Dwg. 3343, Sh. 4.
6. Burns & Roe Dwg. 3304, Sh. 26.
7. Burns & Roe Dwg. 3304, Sh. 23.
8. Burns & Roe Dwg. 3024, Sh. 20.
9. Instruction Manual, Tektronix Model 1502 Time Domain Reflectometer.
10. Instruction Manual, Hewlett Packard Model 4274 Multifrequency LCR Meter.
11. Instruction Manual, Hewlett Packard Spectrum Analyzer (Model 141T, 8553B, 8552B Modules).
12. Instruction Manual, Nicolet Model 444A-26 Spectrum Analyzer.
13. Instruction Manual, Tektronix Model 335 Oscilloscope.
14. Instruction Manual, Lockheed Store-4 Recorder.
15. Instruction Manual, Tektronix SC502 Oscilloscope.
16. TEC Composite Electrical Connection Diagram, CF-1-PT3 (see attachment).

SIGNAL	CABLE	CABINET 156/
+ Sig	IT1720I	TB 2-9-4/4
- Sig	IT1720I	TB 2-9-4/5
SHLD	IT1720I	TB 2-9-4/3

#### STEPS

1. Notify Shift Supervisor/Shift Foreman of start of test on CF-1-PT3.
2. Verify power is applied to CF-1-PT3.
3. Record present reading from CF-1-PT3 Readout Module.



# TEC

# TITLE

# IN-SITU MEASUREMENTS OF CABLES AND SIGNALS FROM CORE FLOOD TANK PRESSURE CF-1-PT3

# NO. TP-112

# REV. 0

# Page A-7

SIGNAL	READING IN PSI
CF-1-PT3 Readout	<del>45</del> PSI 16Z

- Remove all power from CF-1-PT3.

*[Signature]* 7/25/80  
Signature/Date

Lift lead on


- Open ~~link~~ TB 2-9-4/4<sup>5</sup> in Cabinet 150.

*[Signature]* 7/25/80  
Signature/Date

Lifted lead on

- Insert TEC test fixture (100 ohm, 1.0% resistor) across open link TB 2-9-4/4 per Figure 6-1 to convert 10-50 mA signal to voltage.

FIGURE 6-1.



NOTE: This circuit converts the 10-50 ma signal to 1-5 V for testing.

TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT3

NO. TP-112

REV. 0

Page A-8

7. Apply power to CF-1-PT3 and wait 10 minutes for instrument warm-up.
8. Record present reading from CF-1-PT3 Readout Module.

SIGNAL	READING IN PSI
CF-1-PT3 Readout	170 PSI

9. Connect\* differential Conditioning Amplifier (TEC Model 901) to the Core Flood Tank Pressure (TB 2-9-4/4; in Cabinet 150). Connect Model 901 output to FM Recorder and record Signal for 30 minutes. Remove amplifier and FM recorder when completed.

\*NOTE: Connection across banana jacks 1&2 of current-to-voltage test fixture (see Step 6).

10. Using a Keithley Model 177 DMM (or equivalent, Range 0-2000 V, Precision  $\pm 1\%$ ) measure the DC Voltage at the following test point.

<u>SIGNAL</u>	<u>CABINET 156</u>	<u>TEST LEAD</u>	<u>READING</u>
*a.	TB 2-9-4/4 TB 2-9-4/4	(+) (-)	Signal <u>1.89 VDC</u>

\*Across test fixture banana jacks 1&2 (see Step 6).

*Q. T. S. H.*  
Signature/Date 7/20/70

11. Using a Tektronix Model SC502 (or equivalent) oscilloscope observe the waveform at the following test point:

# TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT3

NO. TP-112

REV. 0

Page A-9

SIGNAL	CABINET 150	PARAMETER			
*a.	TB 2-9-4/4 TB 2-9-4/4	+SIG -SIG	Photo <u>112-1</u> Time Base <u>2045</u> Vert Gain <u>20mV</u>	Photo <u>112-2</u> Time Base _____ Vert Gain _____	Photo _____ Time Base _____ Vert Gain _____

\*Across test fixture banana jacks 1&2 (see Step 6).

Sync the oscilloscope and photograph the waveform using up to three time base and vertical gain settings. Mark the back of the photographs with the instrument tag number and parameter measured.

*Q. T. S. A* 9/25/80  
Signature/Date

- Using a Hewlett-Packard Spectrum Analyzer (Models 141T, 8553B and 8552 or equivalent) perform an analysis of the following signal for spectral content:

SIGNAL	CABINET 150	PARAMETER	PHOTO #
*a.	TB 2-9-4/4 TB 2-9-4/4	SIGNAL	<u>112-3</u>

\*Across test fixture banana jacks 1&2 (see Step 6).

Before photographing each scope display adjust analyzer for best spectral resolution. Record critical analyzer parameters e.g., RF bandwidth, RF bandwidth and sweep speed on rear of photograph as well as parameter analyzed.

TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT3NO.  
TP-112

REV. 0

Page A-10

PHOTO # 112-3

SPECTRUM IDENTFREQUENCYAMPLITUDEREMARKS

BANDWIDTH SCAN WIDTH INPUT ATTEN SCANTIME LOG REF SENS  
 3KHz 0.5MHz  $\frac{H7}{DIV}$  0 1 SEC -20db 0

*[Signature]* 9/25/80  
 Signature/Date

13. Using the Nicolet Model 444 FFT Analyzer (or equivalent) perform FFT analysis of signals for the following test point:

<u>SIGNAL</u>	<u>CABINET 150</u>	<u>PARAMETER</u>	<u>PHOTO #</u>
*a <sub>2</sub>	TB 2-9-4/4 TB 2-9-4/4	SIGNAL	112-4 112-5

100k RANGE

\*Across test fixture banana jacks 1&2 (see Step 6).

*[Signature]* 9/25/80  
 Signature/Date

# TEC

# TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT3

NO. TP-112

REV. 0

Page A-11

14. Inside Cabinet 150 perform usual electronic calibrations using applicable instrument shop procedures. Attach instrument shop calibration data sheet and record any significant adjustments or problems in the space below.

Procedure Step	Remarks
See attached instrument shop procedure data sheet.	

Instrument Shop Procedure No. \_\_\_\_\_

Signature/Date \_\_\_\_\_

15. Remove all power from CF-1-PT3.

*JTS 8/25/80*  
Signature/Date

16. <sup>lift +L</sup> ~~Open links~~ for field wires from Cable IT1720I at TB 2-9-4/3, 4, and 5 (Cabinet 150) and remove test fixture (installed in Step 6).

<u>TERMINAL</u>	<u>SIGNAL IDENT.</u>
TB 2-9-4/4	(+) SIGNAL
TB 2-9-4/5	(-) SIGNAL
TB 2-9-4/3	SHIELD

*JTS 8/25/80*  
Signature/Date

TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT3

NO. TP-112

REV. 0

Page A-12

17. Using the Hewlett-Packard Model 4274 (or equivalent) Impedance Bridge, measure the capacitance and impedance at the following test points:

TEST POINT	FROM	TO
a.	TB 2-9-4/4 (+ Sig)	TB 2-9-4/5 (- Sig)
b.	TB 2-9-4/4 (+ Sig)	TB 2-9-4/3 (SHLD)
c.	TB 2-9-4/5 (- Sig)	TB 2-9-4/3 (SHLD)

Record the data required below:

Test Point	Capacitance			Impedance		
Frequency	100 Hz	1 kHz	100 kHz	100 Hz	1 kHz	100 kHz
a. TB 2-9-4/4:5	3.5 NF	3.3 NF	-3.12 NF	18.2K/-24°	46K/-27°	5.5K/-27°
b. TB 2-9-4/4:3	ERRATIC	28 NF	37 NF	ERRATIC	6K/-40°	43K/-24°
c. TB 2-9-4/5:3	ERRATIC	18 NF 25 NF	34 NF	ERRATIC	6K/-85° 4K/-105°	41K/-86°

Signature/Date

18. Using the Tektronix Model 1502 (or equivalent) TDR unit, perform TDR measurements on three test points and record the data below.

# TEC

# TITLE

## IN-SITU MEASUREMENTS OF CABLES AND SIGNALS FROM CORE FLOOD TANK PRESSURE CF-1-PT3

NO. TP-112  
REV. 0

Page A-13

Test Point	Instrument Settings	Strip Chart Number
	Ampl Range Mult	
a. TB 2-9-4/4:5 (+ Sig: - Sig)		112-1
b. TB 2-9-4/4:3 (+ Sig: SHLD)		112-2
c. TB 2-9-4/5:3 (- Sig: SHLD)		112-3

*Q. T. S. A. 4/25/60*  
Signature/Date

19. Using the Keithley Model 144 (or equivalent DMM) perform resistance measurements on the test points specified and record values in the space provided.

*20K RANGE*

TEST POINT	FROM LINK	TO LINK	POLARITY	POLARITY
			From = +; To = -	From = -; To = +
TEST POINT	FROM LINK	TO LINK	RESISTANCE	RESISTANCE
a.	TB 2-9-4/4	TB 2-9-4/5	OPEN	OPEN
b.	TB 2-9-4/4	TB 2-9-4/3	OPEN	OPEN
c.	TB 2-9-4/5	TB 2-9-4/3	OPEN	OPEN

*20K RANGE*

*Q. T. S. A. 4/25/60*  
Signature/Date

TEC

TITLE

IN-SITU MEASUREMENTS OF CABLES AND SIGNALS  
FROM CORE FLOOD TANK PRESSURE CF-1-PT3

NO.

TP-112

REV. 0

Page A-1

- Re termine the
20. ~~Close links for~~ field wires from Cable IT1720I at TB 2-9-4, 4, and 5 (Cabinet 150) and restore power.
  21. Notify the Shift Supervisor/Shift Foreman of the conclusion of testing CF-1-PT3.

I hereby certify that this Test Procedure has been completed as written and that all data has been correctly entered and filed as requested.

TEC Representative

J. T. A. 9/25/60  
Signature/Date

Instrumentation

\_\_\_\_\_  
Signature/Date



## GENERATION CORRECTIVE MAINTENANCE SYSTEM

### CM STATUS ACTIVITY FORM

Page A-15

COMPONENT DESIGNATOR										LOCATION UNIT										JOB TYPE	WORK AUTHORIZATION NUMBER	REQUEST DATE		
SYS	COMP TYPE		COMP ID.	LOOP														MO	DAY	YR				
5	8	12	16	17	22	23	24	28	32	33	38													
C F	I	O P T	3	0	3	6	0	0	2	C M	/ /	C	5	7	3	0	0	9	2	4	8	0		

TXN CD			A C T
1			4
8	0	4	A

ECM NUMBER				
47				51

TXN CD			A C T
1			4
8	0	5	A

P R T Y	RESP 'LOCATION OR CONTRACTOR	P R T Y	ASSISTING CONTRACTOR	P R T Y	ASSISTING CONTRACTOR
66	67	71			
21	0362				

TXN CD			A C T
1			4
8	0	7	A

PURCHASE REQUISITION NUMBER	PURCHASE ORDER NUMBER
59	6667

TXN			ACT
1			4
B	1	0	A

STATUS HOLD								% COMPL	S/M APPROVAL TO COMMENCE WORK			FIELD WORK COMPLETION DATE		
CODE		START DATE		RELEASE DATE					MO	DAY	YR	MO	DAY	YR
39	40	41			45	47	52	53	55	56		61	52	
														67

OUTAGE HOLD  
PART HOLD  
QUALITY CONTROL PART HOLD  
QUALITY CONTROL PROCEDURE HOLD  
OPERATIONS HOLD  
CHANGE MODIFICATION HOLD  
ENGINEERING HOLD  
PLANNING HOLD  
  
MANPOWER NOT AVAILABLE  
AT PORC  
AT QUALITY CONTROL  
AT UNIT SUPERINTENDENT  
AT READING  
POST MAINTENANCE TEST HOLD  
AT ALABA